Queen Anne's County Historic Site Summary Sheet

Survey No:

QA-498

Name:

Arrington Road House

Location:

100 Arrington Road, Queenstown, Maryland

Date:

1860

Access:

Private

Description:

The Arrington Road house is a two-story frame building with side-gabled roof. The building is three bays wide and has a centered gable on the front. Windows are six-over-six, double-hung sash with wood sills and lintels. Roof is clad in composition shingles. There is an enclosed one-room porch on a concrete slab at the main entry. The building is clad in vinyl siding, and has been completely remodeled on the interior.

Significance:

This building has been evaluated under National Register of Historic Places Criteria A, B, and C. It does not meet the requirements for significance under Criterion C for its architectural merit because of its extensive alteration. It is not known to have been associated with significant historical events or persons, and is not, therefore, eligible for listing in the NRHP under Criteria A or B.

MARYLAND HISTORIC	AL TRUST
Eligibility Recommended Comments:	Eligibility Not Recommended XX
Reviewer, OPS: Reviewer, NR Program: Reviewer, NR Program:	Date: 12/18/98

dud

Maryland Historical Trust MARYLAND INVENTORY OF State Historic Sites Inventory Form

Survey No. QA-498

Magi No.

DOE __yes x_no

1. Nam	e (indicate pref	erred name)		
historic				
and/or common	100 Arrington Road			
2. Loca	ation			
street & number	100 Arrington Road			not for publication
city, town	Queenstown	$\underline{\mathbf{x}}$ vicinity of	congressional district	
state	Maryland	county	Queen Anne's	
3. Clas	sification			
Category district building(s) structure site object		Status _X occupied unoccupied work in progress Accessible _X yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park park private residence religious scientific transportation other:
4. Own	er of Propert	y (give names a	nd mailing addresse	es of <u>all</u> owners)
name James	and Genenvieve Roy			
street & number	3301 Lone Point Road	i	telephone n	
city, town	Stevenson	state	and zip code Maryl	and 21666
5. Loca	ation of Lega	Description	on	
courthouse, regis	stry of deeds, etc. Queen Ar	nne's County Regi	stry of Deeds	liber MVM 376
street & number				folio 120
city, town Ce	ntreville		state	MD
6. Repr	esentation in	n Existing	Historical Surv	reys
title _N /A				
ate			federal sta	te county local
depository for su	rvey records			
city, town			state	

I. DESCI	ibrion			Buivey No	• QA-498
ondition		Check one	Check one		

excellent	deteriorated	unaltered	original s	site	
good	ruins	altered	moved	date of move	
fair	unexposed				

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

This former dwelling is located close to U. S. Route 50 on the south side of the road in Queen Anne's County on Maryland's Eastern Shore. The building faces south with its rear elevation facing Rte. 50. It currently houses the offices of the Economy Tree Service.

This building is two stories with a side-gabled roof that is clad in composition shingles. There is an interior brick chimney at each end of the ridge line of the roof. The building is three bays wide and has a centered gable in the front. The gable has a single round-arched, six-light window with board in the arch. The windows throughout the building are six-over-six, double-hung sash. The main entry has an enclosed one-room porch on a concrete slab and a shed roof. The enclosed porch appears to be a modern addition. The east elevation of the building has one window on each floor, placed at the northeast corner. The west elevation has no openings. On the north elevation, facing Rte. 50 are two doors and one window on each floor, placed asymmetrically in the northwest third of the elevation. One door is centered; the other is located at the northeast corner. Both doors have board and batten in the bottom and windows in the top. The centered door has six lights arranged three-by-three in a fixed sash and a two-light transom. The corner door has three horizontal lights in the top half of the door. The entire building is clad in vinyl siding. The interior recently has been completely renovated. It appears that when the building was renovated, two windows on the northeast third of the north elevation were covered over with siding and the window on the first floor was converted to a door. The foundation has been parged and the basement windows on the west have been filled in with brick. There is a modern shed on this property also.

Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799 X 1800–1899 1900–	Areas of Significance—C archeology-prehistoric archeology-historic x agriculture x architecture art commerce communications	heck and justify below community planning conservation economics education engineering exploration/settlemen industry invention	landscape architecture law literature military music at philosophy politics/government	religion cup science cup sculpture cup social/ humanitarian cup theater cup other (specify)
Specific dates		Builder/Architect		
a	icable Criteria: x_A nd/or icable Exception:A		EFG	
Leve	1 of Significance:	national state	x local	

Survey No.QA-498

Significance

Prepare both a summary paragraph of significance and a general statement of history and support.

The house at 100 Arrington Road constructed ca. 1859, is associated with the period of Agricultural Industrial Transition (A.D. 1815-1870), and the themes of Agriculture and Architecture. The house has been evaluated under National Register of Historic Places (NRHP) Criteria A, B, and C to determine its eligibility for listing in the NRHP and the Maryland Inventory of Historic Places (MIHP). The house has been extensively altered both inside and outside. The original two-over-two, double-hung sash windows have been replaced by six-over-six, double-hung sash. Other windows have been filled in. A modern one-room enclosed entry porch has been added to the front of the building. The entire building is currently clad in vinyl siding that does not appear to be in keeping with the original siding. There are no remaining agricultural fields associated with the property. There are no known associations of the house with significant historic events or persons. Therefore, it is recommended that the house at 100 Arrington Road not be considered eligible for listing in the NRHP or the MIHP under Criteria A, B, or C.

The house at 100 Arrington Road is situated to the southeast of Queenstown on the road leading to Wye Mills and points further south. Queenstown served as the seat of Queen Anne's County from 1706 until 1782 when Centreville was chosen as county seat. Queenstown, however, continued to be an important center for local trade during the nineteenth century. The house was constructed during the period of Agricultural - Industrial Transition (A.D. 1815-1870), the economy of Queen Anne's County was based primarily on agricultural goods, such as grains. Farming methods were being improved by the 1820s through the used of fertilizers and crop rotation. Local agricultural products were transported to the market at Baltimore via steamboat which operated from Queenstown beginning in 1820. Although plans for a railroad on the eastern shore of Maryland were made during the 1830s, they were not realized until after the Civil War, and no line serviced the project area vicinity until 1896.

Although this house is reported to have been in existence, it does not appear on the 1877 Atlas for Queen Anne's County. It is likely however, that the house was originally part a small self-sufficient farm which produced agricultural goods for subsistence and sale. The present owner, James Roy, has owned the property for five years and has remodeled the interior for use as the offices of the Economy Tree Service. Roy reported that the house had previously been used as a store (Roy, personal communication 1998).

9. Ma	jor Bibliogr	aphica	I Refere	nces	Survey No. QA-498	
Maryland H 1992 Mar	in the same of the				THT, Crownsville, MD.	
Roy, James 1998 Per	sonal Communication	with A. Co	rampton and M	. Pappas, J	January 1998.	
Wesler, Ki 1981 The	t W. et. al. M/DOT Archeol. Res	sources Sur	vey, Vol. 1:	Eastern Sho	ore. MHT, Manusc. Ser. 5	
10. G	eographica	I Data				
Acreage of n	ominated property $1es$	ss than 1	***************************************			
Quadrangle i	name Wye Mills	_		Qua	adrangle scale 1:24000	
UTM Referen	ces do NOT complete	e UTM refer	ences			
Zone Ea	asting Northing		B L Zone	Easting	Northing	
c		لبيا	D			
E			F			
G L			н 🗀			
Verbal bour	ndary description and j	ustification				
The bounda	ary to include the l	house only.				
List all stat	es and counties for pro	perties overl	apping state or	county bound	laries	
state		code	county		code	
state		code	county		code	- ··
11. F	orm Prepare					
/****	Alice C. Crampton		storian/Archi	tectural H	ISCOLIAN	
name/title	Madeleine Pappas,	nistorian				
organization	Parsons Engineerin	g Science,	Inc.	date Jan	uary 27, 1998	
street & numb	per ¹⁰⁵²¹ Rosehaven S	treet		telephone (7	03) 591–7575	
city or town	Fairfax			virg state	inia 22030	
			•			
	The Maryland Histo		-	_		
	an Act of the Mar	yland Legis	lature to be	found in th	ne Annotated	
	•	yland Legis	lature to be	found in th	ne Annotated	
	an Act of the Mar	yland Legis Article 41	lature to be , Section 181	found in the KA, 1974 s	ne Annotated supplement.	

Maryland Historical Trust return to:

Shaw House

21 State Circle Annapolis, Maryland 21401 (301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCD
100 COMMUNITY PLACE CROWNSVILLE, MD 21032-2023 514-7600

QA-498 Arrington Road House Queenstown, Maryland

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

HISTORIC CONTEXT

Geographic Organization:

Eastern Shore

Chronological/Development Period:

Agricultural-Industrial Transition

(1815-1870 A. D.)

Historic Period Themes:

Agriculture; Architecture

Resource Type:

Category:


Building(s)

Historic Environment: Rural

Historic Function(s) and Use(s):Domestic (single dwelling)

Known Design Source: None

QA-498 100 ARRINGTON ROAD QUEENSTOWN QUEEN ANNE'S COUNTY SITE PLAN PLINGTON





QA-498 Queer Anne's County MD Rita Suffness 10-29-97 H) 3 HPO

South cast as room

10/3



Ot. 198. 100 Arrington Rd. Queen Anne's County MD Rida Sulfrase 10-39-97

Northwest addrer 2083



Ot-198 10 Arrag tor Road Queen Anne's County, MD Rita Suffress 10-29-77 MDSHFO Southeast Corner showing south (front) elevation 3 of 3